

**ADVERTISEMENT FOR BID**  
**Town of Pineville**  
**Lake Park Sidewalk Improvements**

Bids will be received by Pineville Parks and Recreation at 1000 Johnston Drive, Pineville, North Carolina, until 3:00pm on **Wednesday, December 16, 2015** for constructing and completion of the following project:

Design and engineer drawings for storm, curb, retaining wall and pier along Lake Drive, in the Pineville Lake Park, Pineville NC 28134.

The project will also include:

- 15" pipe installed at Lake Dr. cul-de-sac
- 15" FES
- Rip Rap
- Catch basin installed on Lake Dr., doghouse catch basin installed on Lake Dr. tied into existing storm drain
- Asphalt repairs for curb and storm installation
- Valley curb installed on Lake Dr. (includes grading and backfill)
- Demo existing sidewalk, wood retaining wall and ballast
- Install and re-grade soil for new key-stone retaining wall 6' sf to raise sidewalk to code along Lake Dr.
- Install wood pier 72' by 20'
- Remove existing black aluminum fence and re-install
- Furnish silt fence, traffic signage, clean streets. Seed and straw graded areas

All work must meet the minimum standards set forth in the Town of Pineville's Land Development Standards Manual.